


# **HLL Temporary Limitations Notice**

TO:	ALL PILOTS	DATE:	14 February 2023
TLN NUMBER:	01 - 2023		
SUBJECT:	Shell Shearwater with Valaris 122 close by		

#### 1. Comments

The Valaris 122 (V122) drilling rig/jack-up will be carrying out drilling activities close to the Shell Shearwater Platform. The V122 will arrive on location from 14th February 2023 out with the Shearwater 500m zone, but within the Obstacle Free Sector. The location is approximately 680m to the West of the Shearwater Platform. It is estimated that the drilling operation will commence in February 2023 and last approximately 7 months until the end of September 2023.

### 2. Photo/Dwg







Form 09 Rev 01 August 2021

## 3. Existing HLL limitations

### Shearwater

Wind (T°)	Kts	Limitation /Comment		Non-Compliances
005-080		Platform  • Possible turbulence (turbine exhaust)  Turbulence reports requested to assess above  • Table 1(T) if overflight Fire monitor platforms unavoidable.  • Approved friction surface - no net.	5:1	East & West Fire monitor platforms extend 4.5m from SLA

### Valaris 122

Wind (T°)	Kts	Limitation /Comment		Non-Compliances
		<ul> <li>Jack-up</li> <li>Table 1(T) is overflight of 5:1 obstructions unavoidable</li> <li>Poor friction surface - helideck net fitted</li> <li>No helicopter operations whilst under tow</li> </ul>	5:1	Vessel structure Port and Starboard aft of the helideck

### 4. Additional limitations

### Shearwater

Wind (T°)	Kts	Limitation /Comment	Non-Compliances
		Avoid overflight of V122 on	
		Approach/Departure	

### Valaris 122

Wind (T°)	Kts	Limitation /Comment	Non-Compliances
		No additional restrictions	

These restrictions/changes shall remain in force until (unless previously revoked	30 September 2023
or suspended)	

Aircrew are requested to submit voyage reports advising HCA if the information above is incomplete or incorrect